

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Nadel and Gussman, L.L.C
Address: 15 E. 5th St., Suite 3200, Tulsa, OK 74103
Phone: (918) 583-3333 Operator License #: 32638
Type of Well: Gas ^{KCC 4-6-05} BE ^{RBDMS} Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-3-05 (Date)
by: Richard Lacy (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2672 Bottom: 2678 T.D. 3385
2730-2737 Depth to Top: 2681 Bottom: 2684 T.D. 3385
2905-3158 Depth to Top: 2691 Bottom: 2693 T.D. 3385

API Number: 15-129-10367-00-01
Lease Name: Ramsey
Well Number: 1-5
Spot Location (QQQQ): _____ - NE - NE - SW
2310 Feet from ☐ North / ☒ South Section Line
2310 Feet from ☐ East / ☒ West Section Line
Sec. 5 Twp. 33 S. R. 42 ☐ East ☒ West
County: Morton
Date Well Completed: 10-9-54 ^{original} KCC
Plugging Commenced: 3-7-05 ⁴⁻⁶⁻⁰⁵
Plugging Completed: 3-7-05 ^{RBDMS}

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	Gas	0	600	8-5/8	600	
		0	3379	5-1/2	3379	717

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rosel set CIBP + 2 sks cmt 2540 to 2520. 5-1/2 was stuck below 700. Shot loose @ 717 pull to 630. Circ hole w/mud

50 sks 630 to 480. 30 sks 350 to 250. 10 sks 40 - 0. Capped 8-5/8 3' below G.L.

RECEIVED
04-06-05
APR 06 2005

Name of Plugging Contractor: Sargent and Horton Plugging, Inc, License #: 31151

Address: Rt. 1 Box 49 BA, Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Nadel and Gussman, L.L.C.

State of Oklahoma County, Tulsa, ss.

James R. Piland, Manager of Production

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) James R Piland

(Address) 15 E. 5th St., Suite 3200, Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 4th day of April, 20 05

Notary Public

My Commission Expires: 8-1-07