

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Graham County. Sec. 31 Twp. 6S Rge. 22W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Stinemetz "B" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 26 1959
Application for plugging filed September 24 1959
Application for plugging approved September 29 1959
Plugging commenced September 29 1959
Plugging completed September 30 1959
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes A.

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius 2610
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	288'
				5-1/2"	3770'	3770'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3716' - dumped 3 sacks cement.
Bail hole down to 250', set rock bridge; mixed
and dumped 25 sacks cement. Mud up - set rock
bridge with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1959

CONSERVATION DIVISION
Wichita, Kansas

10-21-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address P. O. Box 364 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of ~~owner or contractor~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October 19 59

My commission expires July 7, 1962 Mona L. Bates Notary Public.



f
DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

15-06S-00783-00-00

Stinemetz "B" No. 1
C SW NW Sec. 31-6S-22W
Graham County, Kansas

Total Depth: 3770'

Elevation: 2332' R.B.
Production: D & A

Commenced: 8-29-59 Completed: 9-8-59

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 288' with 225 sacks cement.
Set 5-1/2" Production Pipe at 3770' with 100 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS:</u>	
Surface Clay	100'		
Sand & Shale	1735'	Anhydrite	2679' (/ 347)
Shale & Red Bed	1991'	Heebner	3535' (-1203)
Anhydrite	2025'	Toronto	3561' (-1229)
Shale & Shells	2315'	Lansing	3578' (-1246)
Shale & Lime	3580'	Rotary Total Depth	3770' (-1438)
Lime	3770'		
Total Depth	3770'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *Al Bacon*
Vice-President

Subscribed and sworn to before me this 6th day of October, 1959.

My Commission Expires:

July 7, 1962

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1959

CONSERVATION DIVISION
Wichita, Kansas

Mona L. Latier
Mona L. Latier-Notary Public