

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
DEC 17 1976
CONSERVATION DIVISION
WICHITA, KANSAS

API Number 15 - 065 - 20884 - 00 - 00 (of this well)
Lease Owner The Maurice L. Brown Co.
Address 1500 Vickers KSB&T Bldg., 125 N. Market, Wichita, Kansas 67202
Lease (Farm Name) KEISWETTER Well No. 1
Well Location SE NE Sec. 27 Twp. 6S Rge. ~~EX~~ 22W (W)
County Graham County Total Depth 3982' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 9:00 p.m. 12-10-76

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Gerrell Veatch Address 38 Walnut Drive, Hill City, Ks.

Plugging Contractor Abercrombie Drilling, Inc. License No. _____
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:
Name The Maurice L. Brown Co.
Address 1500 Vickers KSB&T Bldg, 125 N. Market, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr
Applicant or Acting Agent
Jerry A. Langrehr, Exec. V.P.
Date: December 16, 1976

CONTRACTOR'S WELL LOG 15-068-20884-00-00

OPERATOR: The Maurice L. Brown Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KEISWETTER #1
 LOCATION: SE NE, Section 27-6S-22W
 Graham County, Kansas
 SPUD DATE: 11-27-76
 COMPLETION DATE: 12-10-76

0	72	Surface Clay & Sand
72	247	Sand & Shale
247	1535	Shale
1535	1721	Sand
1721	1974	Shale
1974	2006	Anhydrite
2006	3006	Shale
3006	3540	Shale & Lime
3540	3572	Lime & Shale
3572	3744	Lime
3744	3825	Lime & Shale
3825	3887	Lime
3887	3923	Lime & Shale
3923	3961	Sand
3961	3982	Granite Wash
	3982	Rotary Total Depth

Spud at 2:00 p.m. 11-27-76. Drilled 247' of 12 1/4" hole. Ran 6 jts. of 8 5/8" surface casing - tally 239'. Set at 247' K.B. Cemented with 190 sx. of Class "A" Cement, 3% Ca. Cl. Plug was down at 9:00 p.m. 11-27-76.

T.D. 3982', Set 1st plug at 1000' with 70 sx., 2nd plug at 250' with 20 sx., 3rd plug at 40' with 10 sx., 50/50 posmix, 6% gel. Plug was down at 9:00 p.m. 12-10-76.

SAMPLE TOPS:
 Anhydrite 1974'
 B/Anhydrite 2006'

12-17-76

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice-President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KEISWETTER #1, SE NE, Section 27-6S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jerry A. Langrehr
 Jerry A. Langrehr, Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of December, 1976.

COPY

Kathy S. Goertz
 Kathy S. Goertz, Notary Public



State of Kansas



15-065-20884-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

December 15, 1976

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Keiswetter
Description	C SE NE Sec. 27-6-22W
County	Graham
Total Depth	3982
Plugging Contractor	Abercrombie Drilling Co., Inc.


Maurice L. Brown & I. Wayne Woolsey
1500 Vickers-KSB&T Building
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.