

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION

MAR 03 1976
3-3-76
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-065-20814-00-00 (of this well)
Lease Owner F & M Oil Company
Address 505 Union Center, Wichita, Kansas 67202
Lease (Farm Name) BOWERS Well No. #1
Well Location C NW NE Sec. 9 Twp. 6S Rge. (E) 23 (W)
County Graham Total Depth 3840' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 1:30 p.m. February 20, 1976

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Don Favinger Address Hill City, Kansas 67642

Plugging Contractor Abercrombie Drilling, Inc License No. #746

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company

Address 505 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr
Applicant or Acting Agent
Jerry A. Langrehr
Exec. Vice President
Date: _____

CONTRACTOR'S WELL LOG

15-065-20814-00-00

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BOWERS #1
 LOCATION: C NW NE Section 9-6S-23W
 Graham County, Kansas
 SPUD DATE: February 13, 1976
 COMPLETION DATE: February 20, 1976

| | | |
|------|------|--------------------|
| 0 | 225 | Clay & Sand |
| 225 | 258 | Shale |
| 258 | 481 | Sand & Shale |
| 481 | 725 | Shale |
| 725 | 2078 | Shale & Sand |
| 2078 | 2110 | Anhydrite |
| 2110 | 2922 | Shale |
| 2922 | 3595 | Shale & Lime |
| 3595 | 3665 | Lime & Shale |
| 3665 | 3730 | Shale & Lime |
| 3730 | 3840 | Lime |
| | 3840 | Rotary Total Depth |

Spudded in @ 10:45 a.m. Drilled 258' of 12 1/4" hole. Ran 6 jts. used 8 5/8" casing. Tallied 250.78'. Set @ 258' with 165 sx. Quick-Set Cement. Cement circulated. Plug was down @ 3:30 p.m. February 13, 1976.

Plugged and Abandoned: 1st Plug was Set @ 950' with 70 sx. cement; 2nd Plug was Set @ 250' with 20 sx. cement; 3rd Plug was Set @ 40' with 10 sx. cement. State Plugger: Gilbert Balthazor. Plug was down @ 1:30 p.m. February 20, 1976.

SAMPLE TOPS:
 Anhydrite 2078'
 B/Anhydrite 2110'

RECEIVED
 STATE COMMISSIONER OF GEOLOGY
 MAR 03 1976
 3-3-76
 GENERAL INVESTIGATIVE DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Exec. Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BOWERS #1, C NW NW, Section 9-6S-23W, Graham County, Kansas.


ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 1st day of March, 1976.

Diane Steincamp
 Diane Steincamp - Notary Public

My Commission Expires: February 18, 1980





State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

February 25, 1976

WELL PLUGGING AUTHORITY

| | |
|---------------------|----------------------------|
| Well No. | 1 |
| Lease | Bowers |
| Description | C NW NE Sec. 9-6-23W |
| County | Graham |
| Total Depth | 3840 |
| Plugging Contractor | Abercrombie Drilling, Inc. |


F & M Oil Company, Inc.
505 Union Center
Wichita, KS 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P. O. Box 9, Rt. #1, Palco, KS 67657
is hereby assigned to supervise the plugging of the above named well.