

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1978  
9-26-78  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 065-21096-0000 (of this well)  
Lease Owner F & M Oil Company  
Address 505 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) Shuck Prospect Well No. #1  
Well Location NE SW NW Sec. 9 Twp. 6 S Rge. (X) 23 (W)  
County Graham Total Depth 3840' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin September 21, 1978, 1:00 p.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Harold Maley Address 216 E. McFarland, Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. \_\_\_\_\_

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company

Address 505 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent

Jack L. Partridge, Ass't. Secretary-Treas.  
Date: September 25, 1978

OPERATOR: F & M Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Shuck Prospect #1  
 LOCATION: NE SW NW Section 9-6S-23W  
 Graham County, Kansas  
 SPUD DATE: September 12, 1978  
 COMPLETION DATE: September 21, 1978

0	225	Surface clay & sand
225	269	Shale
269	2066	Shale & sand
2066	2100	Anhydrite
2100	2505	Shale
2505	2830	Shale & lime
2830	3347	Lime & shale
3347	3523	Lime
3523	3676	Lime & shale
3676	3690	Lime
3690	3710	Lime & shale
3710	3763	Lime
3763	3790	Lime & shale
3790	3820	Lime
3820	3840	Lime & shale
	3840	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 26 1978

CONSERVATION DIVISION  
 Wichita, Kansas

9-26-78

Spud hole at 6:15 p.m., September 12, 1978. Drilled 269' of 12 1/4" hole. Ran 6 joints of 8-5/8" - 28# surface casing. Set at 268' K.B. with 180 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Job complete at 11:30 p.m., September 12, 1978.

T.D. 3840'. Set first plug at 1000' with 70 sacks, second plug at 240' with 20 sacks, third plug at 40' (solid bridge) with 10 sacks. Cemented with 50-50 posmix, 6% gel. Job was complete at 1:00 p.m., September 21, 1978. State plugger, Leo Massey.

SAMPLE TOPS:

Anhydrite 2066'  
 B/Anhydrite 2100'

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Shuck Prospect #1, NE SW NW Section 9-6S-23W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 25th day of September, 1978.

Sandra Richman  
 Sandra Richman, Notary Public



State of Kansas



15-065-21056-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

September 26, 1978

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Schuck
Description	NE SW NW Sec. 9-6-23W
County	Graham
Total Depth	3840
Plugging Contractor	Abercrombie Drilling


F & M Oil Co., Inc.  
505 Union Center  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601  
is hereby assigned to supervise the plugging of the above named well.