

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15-065-21298-00-00 (of this well)  
Lease Owner F & M Oil Company  
Address 422 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) WYRILL Well No. 1  
Well Location NE SE Sec. 5 Twp. 6S Rge. 23 (E)      (W) X  
County Graham Total Depth 3830' Field Name       
Oil Well      Gas Well      Input Well      SWD Well      Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 8:45 p.m. 08-31-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Harold Maley Address 216 E. McFarland, Hill City, KS

Plugging Contractor Abercrombie Drilling, Inc. License No. RECEIVED  
STATE CORPORATION COMMISSION

Address 801 Union Center, Wichita, Kansas

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company

Address 422 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed:

Jack L. Partridge

Applicant or Acting Agent

Jack L. Partridge, Asst. Sec.-Treas.

Date: 09-09-80

SEP 11 1980

9-11-80  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

15-065-21298-00-00

OPERATOR: F & M Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: WYRILL #1  
 LOCATION: NE SE, Section 5-6S-23W  
 Graham County, Kansas  
 SPUD DATE: 08-25-80  
 COMPLETION DATE: 08-31-80

0	295	Clay Sand & Shale
295	500	Shale
500	1500	Shale & Sand
1500	1580	Shale
1580	1989	Sand & Shale
1989	2056	Shale
2056	2088	Anhydrite
2088	2953	Shale
2953	3645	Shale & Lime
3645	3830	Lime
	3830	Rotary Total Depth

Spud hole @ 2:45 p.m. 08-25-80. Drilled 295' of a 12-1/4" hole. Ran 7 joints of 8-5/8" - 20# casing (tally 285'). Set @ 292' RTD. Cemented with 235 sx. of common, 3% c.c., 2% gel. Cement did circulate. Plug was down @ 7:30 p.m. 08-25-80.

T.D. 3830'. Set 1st plug @ 1200' with 60 sx., 2nd plug @ 280' with 30 sx., 3rd plug @ 40' solid bridge with 10 sx. rathole with 5 sx., 50/50 posmix, 6% gel. Cement by Sun Cementing. Plug was down @ 8:45 p.m. 08-31-80.

SAMPLE TOPS:

Anhydrite 2056'  
 B/Anhydrite 2088'

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 11 1980

STATE OF KANSAS )  
 ) :SS  
 COUNTY OF SEDGWICK )

CONSERVATION DIVISION  
 Wichita, Kansas

9-11-80

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WYRILL #1, NE SE, Section 5-6S-23W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 9th day of September, 1980.



Jeannette A. Metheny  
 Jeannette A. Metheny, Notary Public

State of Kansas



15-065-21298-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

September 15, 1980

WELL PLUGGING AUTHORITY

Wyrill #1  
NE SE, Sec. 5-6S-23W  
Graham County  
3830'  
Abercrombie Drlg, Inc.


F & M Oil Company, Inc.  
422 Union Center  
Wichita, KS 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,

  
J. LEWIS BROCK, Administrator

Mr. Gilbert Balthazor, Box 9, Palco, KS 67657  
is hereby assigned to supervise the plugging of the above named well