

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

~~15-065-14024-00-00~~
00053-00-01

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1963
1-18-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name W. P. Simmons Oil Co.

Complete Address: Alma, Nebraska.

Lease Name Rush Well No. 1

Location SW-SW-NE Sec. 15 Twp. 6 Rge. (E) (W) 22

County Gra ham Total Depth 3780

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: R & D Casing Pulling Co

Address: Ellinwood, Kansas License No. 236

Operation Completed: Hour 2:30 PM Day 16, Month 1 Year 1963

The Above well was plugged as follows:

209' 8 5/8" Surface cment circulated. 4 1/2"-3780' with 125 Sx cement.
Top perforation- 3563'. Sanded well back to 3550, set 4 Sx cement with
dump bailer. Initial shot @ 2700', circulated oil. Final shot @ 1520'
pulled 4 1/2 " to 600', circulated hole with heavy mud (25 Sx Gel),
displaced 20 Sx cement thru 4 1/2", heavy mud to 180', displaced 20 Sx
cement thru 4 1/2", heavy mud to 30', set plug and 10 Sx cement to bottom
of cellar. Cementing and mudding operations performed by Halliburton
Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/18/63
INV. NO. 6446-W

Signed: H. L. Nichols
Well Plugging Supervisor