

9
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-30022-00-01

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. H. Riggs,

Complete Address: 350 Denver Club Building, Denver, Colorado.

Lease Name LaCerte Well No. 3

Location CSW-SW Sec. 31 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3826

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 3:00 PM Day 22 Month 3 Year 1968

The Above well was plugged as follows:

223'--7" OD Surface casing, cement circulated with 100 Sx.

3824'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforation @ 3756.

Top of Dakota @ 875'.

Sanded well back to 3725' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and

squeezed well using first 14 sacks gel with 3 sacks hulls in initial gel and followed

with 65 Sx. cement from 1100' to 775', then 9 sacks gel from 775' to 250' and followed

with 15 Sx. cement from 250' to 175', then 2 sacks gel from 175' to 50' and finally 10

Sx. cement from 50' to bottom of cellar. Maximum pump-in pressure-650#. Final shut-in

pressure-150#. (Recovered 1400' 4 1/2" casing) Mudding and cementing operations by Knight.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Dickels*
Well Plugging Supervisor

DATE 3/26/68

INV. NO. 7468-W