

15-065-19040-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name E. H. Riggs.

Complete Address 350 Denver Club Building, Denver, Colorado.

Lease Name LaCerte Well No. 1

Location NE 1/4 of SW 1/4 Sec. 31 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3810'

Abandoned Oil Well        Gas Well        Input Well X SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:30 PM Day 25 Month 7 Year 1969

The above well was plugged as follows:

183'--8 5/8" Surface casing, cement circulated .  
3809'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to 3786'. Top  
perforations from 3689' to 3690'.

Pushed plug to 3650', built sand bridge from 3650' to 3620' and set 5 Sx. cement with  
dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 8  
sacks gel and followed with 100 Sx. cement from 1100' to 775' then 1 1/2 sacks gel from  
775' to 220' and followed with 20 Sx. cement from 220' to 160' then 3 sacks gel from  
160' to 140' and finally 10 Sx. cement from 140' to bottom of cellar. Maximum pump-in  
pressure-350#. Final shut-in pressure-150#. (Mudding and cementing by ~~Standard~~ Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 7/28/69

INV. NO. 165-W