

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-069-20673-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

6-13-74
RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Irv Hardman & P-S Petro. Co.

Complete Address 403 Insurance Bldg., Wichita, Kansas

Lease Name Hardman Well No. 1

Location Appr N/2 SW NE Sec. 24 Twp. 6 Rge. (E) (W) 23

County Graham Total Depth 3880'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Chief Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 11:30 A Day 11 Month 6 Year 1974

The above well was plugged as follows:

RTD 3880' 8 5/8 csg set at 303' cwc 200 sk. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 315' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 6/13/74
INV. NO. 9303-W