

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-19033-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1963

12-12-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Glickman Oil Company,

Complete Address: 702 So. St. Francis, Wichita, Kansa s.

Lease Name Pratt Well No. 1

Location CNW-NE Sec. 24 Twp. 6 Rge. (E) (W) 23

County Graham Total Depth 3840

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Barnes & Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas. License No. 9

Operation Completed: Hour 3:00PM Day 5 Month 12 Year 1963

The Above well was plugged as follows:

223' --8 5/8" Surface pipe, cement circulated with 150 Sx. 3839' --5 1/2"
production casing cemented with 100 Sx. Well plugged back to 3820', Top
perforations 3704' to 3708'.

Shot 5 1/2" off @ 3267' and spotted 95 Bbl. oil with 10 Sx. gel. Pulled 5 1/2"
to 660' and circulated heavy gel mud (19 Sx. gel). Pulled 5 1/2" to 540' and
displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 210' and displaced 20 Sx.
cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/12/63
INV. NO. 8272-U

Signed: W. L. Nichols
Well Plugging Supervisor