

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20683-00-00

7-9-74  
RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company  
Complete Address 617 Union Center Wichita, Kansas  
Lease Name Niehans ~~Niehans-Middleton~~ Well No. 1  
Location C SW SE Sec. 20 Twp. 6 Rge. (E) (W) 23  
County Graham Total Depth 3651'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor        Co, Tools         
Address        License No.       

Operation Completed: Hour 9:15 P Day 7 Month 7 Year 1974

The above well was plugged as follows:

RTD 3651' 8 5/8 csg set at 177' cwc 125 sk.  
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/10/74  
INV. NO. 9487-W