

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-30004-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1965
1-25-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Demuth Well No. 1

Location CSW-NW Sec. 25 Twp. 6 Rge. (E) (W) 23

County Graham Total Depth 3882

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 12:30AM Day 22 Month 1 Year 1965

The Above well was plugged as follows:

239'--8 5/8" Surface pipe, cement circulated with 140 Sx.

Circulated hose with heavy mud, set plug @ 550' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulla and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 1/26/65

INV. NO. 586-W

Signed: W. L. Nichols
Well Plugging Supervisor