

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20142-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

5-20-68
RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Meyer-Heitz Well No. 1

Location NW-NW Sec. 28 Twp. 6 Rge. (E) (W) 23

County Graham Total Depth 3946

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 8:45AM Day 17 Month 5 Year 1968

The Above well was plugged as follows:

262'--8 5/8" Surface pipe, cement circulated with 225 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 280' and displaced 20 Sx. cement thru DP from
280' to 220'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 5/20/68
INV. NO. 7982-W