



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20767-06-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1974

CONSERVATION DIVISION
Wichita, Kansas

12-9-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name F & M Oil, Inc.

Complete Address 603 Union Center, Wichita, Kansas

Lease Name Gordon Well No. 1

Location NW SE Sec. 27 Twp. 6 Rge. (E) (W) 23

County Graham Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg

Address Wichita, Kansas License No.

Operation Completed: Hour 11 P Day 7 Month 12 Year 1974

The above well was plugged as follows:

RTD 3865' 8 5/8 csg set at 214' cwc 150 sk.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at ¹¹³⁵ thru drill pipe.

Heavy mud to 185' -set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set
cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Massey
Well Plugging Supervisor

DATE 12/13/74
INV. NO. 457-W