



15-068-30044-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUL 28 1969

CONSERVATION DIVISION  
Wichita, Kansas

7-28-69

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: E. H. Riggs,

Complete Address: 350 Denver Club Building, Denver, Colorado.

Lease Name: LaCerte Well No. 4

Location: CS#-SW Sec. 31 Twp. 6 Rge. (E)(W) 22

County: Graham Total Depth 3870' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clarke was instructed to plug the well as follows:

222'--7" Od Surface casing, cement circulated with 110 Sx.  
3869'--4 1/2" Production casing cemented on bottom with 100 Sx. No plug back nor perforations indicated.

Push plug to 3650' sand back to 3620' and set 3 Sx. cement with dump bailer.

Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 13 sacks gel and 85 Sx. cement, staged.

Very truly yours,

Conservation Division Agent