



15-065-00268-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

7-28-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: E. H. Riggs,

Complete Address: 350 Denver Club Building, Denver, Colorado.

Lease Name: LaCerte Well No. 2

Location: NW-NW-SW Sec. 31 Twp. 6 Rge. (E)(W) 22

County: Graham Total Depth 3990' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clarke was instructed to plug the well as follows:

183'--8 5/8" Surface casing, cement circulated with 140 Sx.

3989'--4 1/2" Production casing cemented on bottom with 100 Sx. No plug back nor perforations indicated.

Push plug to 3650', sand back to 3620' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls and 30 sacks gel and 130 Sx. cement, staged.

Very truly yours,

*K. L. Nichols*

Conservation Division Agent