



00053-00-01
15-065-14024-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1963

1-18-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Virgil Kelso of R & D Casing Pulling Co has this

date requested permission to plug the following described well:

W. P. Simmons Oil Co

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: W. P. Simmons Oil Co.

Complete Address: Alma, Nebraska

Lease Name: Rush Well No. 1

Location: SW-SW-NE Sec. 15 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3780 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

Sand well back to 3550, set 4 Sx cement with dump bailer.

Pull 4 1/2" casing to 600', circulate hole with heavy mud,

Displace 20 Sx cement thru casing @ 600'.

Pull casing to 180' displace 20 Sx cement thru Casing.

Pull casing to 30', set bridge and fill to bottom of
cellar with cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent