

State of Kansas



15-065-30022-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellenger of Knight Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Dellenger guarantees payment of the plugging fee.

Operator's full Name: E. H. Riggs,

Complete Address: 350 Denver Club Building, Denver, Colorado.

Lease Name: LaGerte Well No. 3

Location: CSW-SW Sec. 31 Twp. 6 Rge. (E)(W) 22

County Graham Total Depth 3826 Oil Well X

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Dellenger was instructed to plug the well as follows:

223'--7" OD Surface casing, cement circulated with 100 Sx. (6 1/4" Hole).

Top of Dakota @ 875'.

3824'--4 1/2" Production casing cemented with 100 Sx. Top perforation

@ 3756'.

Sand well back to 3725' and set 3 Sx. cement with dump bailer. Pull
4 1/2" casing and squeeze well using 25 sacks gel plus 3 sacks hulls and
90 Sx. cement, staged.

Very truly yours,

Conservation Division Agent