



15-065-19040-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Gsg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: E. H. Riggs.

Complete Address: 350 Denver Club Building, Denver, Colorado.

Lease Name: LaCerte Well No. 1

Location: NE/4-SW/4 Sec. 31 Twp. 6 Rge. (E)(W) 22

County: Graham Total Depth 3810' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Clarke was instructed to plug the well as follows:

183'--8 5/8" Surface casing, cement circulated.

3809'--5 1/2" casing cement on bottom with 100 Sx. Well plugged back to 3786'. Top perforations from 3689' to 3690'.

Push plug to 3650', build sand bridge from 3650' to 3620' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 Sx. hulls, 25 sacks gel and 130 Sx. cement, staged.

Very truly yours,

Conservation Division Agent