

State of Kansas



15-065-20128-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1968
CONSERVATION DIVISION
Wichita, Kansas
3-26-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc., & J. M. Stewart,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Peel-Pratt Well No. 1

Location: SE-SE-SW Sec. 13 Twp. 6 Rge. (E)(W) 23

County Graham Total Depth 3830 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

237'--7 5/8" OD Surface pipe, cement circulated with 125 Sx. (6 3/4" Hole).
Top Dakota section @ 1080'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 180 Sx.
cement thru DP. Pull DP to 245' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent