



15-065-20673-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027
WICHITA, KANSAS 67217

STATE RECEIVED
JUN 13 1974
CONSERVATION DIVISION
Wichita, Kansas
6-13-74

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Crlg. has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Irv Hardman & P-S Petr. Co.

Complete Address: 403 Insurance Bldg., Wichita, Ks.

Lease Name: Hardman Well No. 1

Location: Appr N/2 SW NE Sec. 24 Twp. 6 Rge. (E)(W) 23

County: Graham Total Depth 3880' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burris was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' and displace

70 sk cmt thru drill pipe. Heavy mud to 315' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent