

State of Kansas



15-065-19033-00-00

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1963

12-12-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling has this

date requested permission to plug the following described well:
Glickman Oil Co.

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Company,

Complete Address: 702 So. St. Francis, Wichita, Kansas.

Lease Name: Pratt Well No. 1

Location: CNW-NE Sec. 24 Twp. 6 Rge. (E) (W) 23

County Graham Total Depth 3840 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Barnes was instructed to plug the well as follows:

223'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3839'--5 1/2" cemented with 100 Sx. Plugged back to 3820', Top
perforations 3704' to 3708'.

Sand well back to 3690' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 660' circulate heavy gel mud, pull 5 1/2" to 600' and
displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 210' and displace
20 Sx. cement thru 5 1/2". Pull 5 1/2", set 5' rock bridge @ 35' and
10 Sx. cement to bottom of cellar.

Very truly yours,

W. A. Nichols