

State of Kansas



15-065-20683-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1974

CONSERVATION DIVISION
Wichita, Kansas

7-9-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Reiter of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg., Co.

Complete Address: 617 Union Center, Wichita, Ks.

Lease Name: ~~Nichans~~ ^{Nichaus} Nichans-Middletom Well No. 1

Location: C SW SE Sec. 20 Twp. 6 Rge. (E)(W) 23

County: Graham Total Depth 3651' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Reiter was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' and displace
70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo Z. Massey
Conservation Division Agent