



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
5-20-68

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this  
date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Meyer-Heitz Well No. 1

Location: NW-NW Sec. 28 Twp. 6 Rge. (E)(W)23

County: Graham Total Depth 3946' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

262'--8 5/8" Surface pipe, cement circulated with 225 Sx.  
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx.  
cement thru DP. Pull DP to 280' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent