

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15472-00-00  
Spot: NESESW Sec/Twnshp/Rge: 11-19S-12W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: AHRENS Well #: 3  
County: BARTON Total Vertical Depth: 3407 feet

Operator License No.: 31528  
Op Name: KELSO, MIKE - OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

PROD Size: 5.5 feet: 3377 200 SX CMT  
SURF Size: 8.625 feet: 244 160 SX CMT

13  
\$110

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/01/2005 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: KELSO, MIKE - OIL, INC. Phone: (620) 938-2943

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 04/01/2005 5:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Sanded to 3075' - spotted 5 sxs cement with dump bailer.  
Shot casing loose at 1700' and pulled to 1425'.  
Mixed and pumped 100 sxs cement with 300# hulls.  
Pulled casing to 700' - mixed and pumped 40 sxs cement with 100# hulls.  
Pulled casing to 250' and circulated cement to surface with 65 sxs cement.  
Pulled casing with hole full of cement to surface.

Perfs:

Top	Bot	Thru	Comments
3128	3188		


RECEIVED  
APR 06 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

**INVOICED**  
DATE 4-6-05  
INV. NO. 2005061375

APR 05 2005

ALADDIN & CROWE

#3

AHRENS

11-19-12W  
NE SE SW

53

Contr. CROWE DRILLING COMPANY

BARTON

County

E.1837 RB Comm. 6-2-50

Comp. 7-21-50

IP

526 BOPD

PHY POT

Tops	Depth	Datum
ANH	660	+1177
LANS	3128	-1291
ARB	3378	-1541
T.D.	3385	-1548

Casing

8" 244  
5" 3382

DST 3128-96, OPEN  
15 MIN, 540' OIL CUT  
MUD: PERF 3194-3201:  
SWB 6 BWPB: SQZ: PERF  
3182-88, 3174-82,  
3167-74, 3148-56,  
3144-48, 3131-35,  
3123-31: ACID 3000:  
CHEYENNE VIEW POOL FLOW 50 BOPB


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

WADICER