

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21035-00-00
Spot: N2SW Sec/Twnshp/Rge: 15-19S-12W
1980 feet from S Section Line, 1320 feet from W Section Line
Lease Name: SCHWERTFEGER Well #: 1
County: BARTON Total Vertical Depth: 3510 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

PROD Size: 4.5 feet: 3506 200 SX CMT
SURF Size: 8.625 feet: 241 175 SX CMT

#114⁰⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: RAMA OPERATING COMPANY, IN Phone: (620) 234-5191

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2005 1:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Log Tech shot off casing at 1690'.
Pulled one joint to 1650'. Well kicked off flowing oil.
Pumped 70 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 750' and pumped 35 sxs cement with 100# hulls.
Pulled to 225' and circulated with 65 sxs cement with 100# hulls.

Perfs:

Top	Bot	Thru	Comments
3451	3456		
3445	3447		
3435	3439		

RECEIVED
APR 06 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

MD

Signed _____
(TECHNICIAN)

APR 01 2005

INVOICED
DATE 4-6-05
INV. NO. 2005061377

MURFIN DRLG. CO.
671 UNION CENTER

#1 SCHWERTFEGER

15-19-12W
C N/2 SW

CONTR WOODMAN-IANNITTI DRLG.CO CTY BARTON

GEOL _____ FIELD CHEYENNE VIEW

E 1867 KB CM 5/21/76 CARD ISSUED 7/15/76 IF P 64 BOPD
CONG 3435-56

	+	+
	+	+
	+	+

API 15-009-21,035

LOG	TOPS	DEPTH	DATUM
*ANH	702	+1165	
*B ANH	725	+1142	
*HEEB	3047	-1174	
*TOR	3061	-1194	
*DOUG	3077	-1210	
BR LM	3157	-1290	
LKC	3173	-1306	
BKC	3424	-1557	
CONG	3434	-1567	
LTD	3507	-1640	
RTD	3510	-1643	
*SAMPLE TOPS			

8 5/8" 241/175sx, 4" 3506/200sx
DST (1) 3161-3207/45-45-45-45, REC 180' G
125' GCSOCWM, (5-10% OIL GRIND OUT) SIP
867-867#, FP 81-132#, BHT 102°
DST (2) 3305-3420/30-30-30-30, REC 120' M
ISIP 657#, FSIP NOT GOOD, IFP 121#, FFP
NOT GOOD
DST (3) 3424-65/45-45-45-45, REC 960' GMW,
(300' FO, 120' VHOGCM, 180' FO, 120' VHOGCM,
120' HOGCM, 120' GO) GR 38°, SIP 406-336#
FP 264-386#, GR 40°
MICT - CO, PBD 3461', SWB DRY, PF 2/3451-
56, 8/3445-47, SWB 5 GOCM&W, ON/FU 525'
SWD DWN & REC 8 1/2 BO, NW, SWB 2 BOPH, NW/2 HRS
PF 8/3435-37, SWB DWN & SWB 2 BO/1ST HR, 3
BO/2ND HR, 2-3/4 BO/3RD HR, 2 1/2 BO/4TH HR,
ON/FU 1250', R&T, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MADICER