

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03953-00-01  
Spot: NWNWSE Sec/Twnshp/Rge: 19-8S-17W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: REEDER Well #: 1  
County: ROOKS Total Vertical Depth: 3394 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 3381 w/150 sxs cmt  
SURF Size: 8.625 feet: 258 w/175 sxs cmt

#110<sup>31</sup>

Well Type: EOR UIC Docket No: E12545.1 Date/Time to Plug: 03/18/2005 9:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix -10% gel - 500# hulls - 24 sxs gel.  
DV at 1309' w/338 sxs.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2005 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing to 3000' - spotted 50 sxs cement with 300# hulls and 24 sxs gel.  
POOH with tubing to 1350' - circulated 90 sxs cement to surface with 300# hulls.  
POOH with tubing - pumpe down 5 1/2" with 35 sxs cement.  
S.I.P. 300#. Pressured 8 5/8" to 600#.

RECEIVED  
APR 06 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel  
(TECHNICIAN)

INVOICED

Form CP-2/3

APR 04 2005

DATE 4-6-05  
INV. NO. 2005066381

CITIES SERVICE OIL COMPANY #1

REEDER

19-8-17W  
NW NW SE

22V

Contr. \_\_\_\_\_ ROOKS \_\_\_\_\_ County

E 1958 Comm. \_\_\_\_\_ Comp. 2-1-52 IP 57 BOPD & 3 BW  
PHY POT

Tops	Depth	Datum
HEEB	3076	-1118
DODGE	3097	-1139
LANS	3118	-1160
ARB	3379	-1421
T.D.	3394	-1436

Casing

8" 258 PMP 35 B0/5 HRS:  
 5" 3381 ACID 2000:  
 PMP 40 B0/24 HRS:  
 DD 3394:  
 ACID 2000:  
 PMP 100 B0 & 7 BW/  
 7 HRS  
 ELM CREEK POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

WADICER