

To: 6 031415  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-21535-00-00  
NE NE SE, SEC. 16, T 6 S, R 22, WAE

TECHNICIAN'S PLUGGING REPORT

Operator License # 5016  
Operator: Energy Prod Inc.  
Name & Address 1100 Bitting Bldg.  
Wichita, Ks. 67202

2310 feet from S section line  
330 feet from E section line  
Lease Name Rush B Well # 1  
County Graham 127.23  
Well Total Depth 3915 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 613

Abandoned Oil Well xx Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso License Number 6050  
Address Chase, Ks.

Company to plug at: Hour: PM Day: 10 Month: Sept Year: 19 90

Plugging proposal received from Vernon  
(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8 set at 613 w/350 sks cwc 4 1/2 set at 3973 w/125 sks. PBTB 3826.

Perf 3704 - 3706. Order sand and common cement. Pull pipe, order 250 sks 65/35 poz

8% gel 500 lbs. hulls. Allied Cement Co. LaRue water trucks.

Ran wireline, hole open thru fish.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30PM Day: 10 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3650 w/4 sks common cement on sand w/bailer.

Recovered 1600 of 4 1/2. Sq 8 5/8 casing w/250 sks cement blend w/500 lbs. hulls mixed into  
max psi 800 lbs. Close in psi 400 lbs. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 3 1990

CONSERVATION DIVISION  
Wichita, Kansas  
10-3-90

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE OCT 05 1990  
INV. NO. 29533

*J. S.*

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow