

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20568-00-01
Spot: NWSW Sec/Twnshp/Rge: 2-31S-35W
1980 feet from S Section Line, 660 feet from W Section Line
Lease Name: CULLISON B Well #: 2-1
County: STEVENS Total Vertical Depth: 5920 feet

Operator License No.: 31914
Op Name: CONTINENTAL RESOURCES, INC.
Address: PO BOX 1032
ENID, OK 73702

CIBP Size: feet: 5640 WITH 2 SX CMT
PROD Size: 4.5 feet: 5905 WITH 325 SX CMT
SURF Size: 8.625 feet: 1606 WITH 950 SX CMT

\$19240

Well Type: EOR UIC Docket No: E27491.1 Date/Time to Plug: 03/28/2005 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 5640' WITH 2 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 500' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2005 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CASING LEAKS FROM 2931-3453'. CIBP @ 5640' WITH 2 SX CMT. 1ST PLUG LOAD HOLE WITH MUD. PUMP 50 SX CMT AT 1700'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 4 1/2" TO 600'. CIRCULATE HOLE WITH MUD & PUMP 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5729	5750		

RECEIVED
APR 04 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1700' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PARTIP
(TECHNICIAN)

INVOICED

DATE 4-5-05
INV. NO. 2005061367

[Signature]
Form CP-2/3