

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,724-00-00
SW-SW-NE, Sec. 15, T 6 S, R 22 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from N/S section line

2210 feet from W/E section line

Operator License # 5016

Lease Name RUSH Well # E-1

Operator: ENERGY PRODUCTION, INC.
Name &
Address 8020 E. CENTRAL, #150
WICHITA, KS. 67206

County GRAHAM

Well Total Depth 3760 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRUG, INC License Number 179

Address 801 UNION CTR. WICHITA, KS. 67202

Company to plug at: Hour: 2:00 AM Day: 8th Month: DEC Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO HAROLD MALEY

(company name) ABERCROMBIE DRUG CO. (phone) 316-681-2786

were: 8 5/8" - 283 FT SP. PUL #/200 COMMON - 2% GEL. 3% CA-CL + 8 5/8" PLUG.
ORDER 180 ST 50/50 Formix 6% GEL. 3% CA-CL AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS ST
1st PLUG @ 1980 FT #/20 ST QNT. -> 2nd PLUG @ 1200 FT #/100 QNT.
3rd PLUG @ 300 FT #/40 ST QNT. -> 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40' #/10 QNT ST
10th IN RAT HOLE (CIRCULATE)

Signed Marion Schmidt (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 AM Day: 8th Month: DEC Year: 1982

ACTUAL PLUGGING REPORT ORDERED - 180 ST 50/50 Formix - 6% GEL. - 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1st PLUG @ 1980 FT #/20 ST QNT. -> 2nd PLUG @ 1200 FT #/100 ST QNT.
3rd PLUG @ 300 FT #/40 ST QNT. -> 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40' #/10 QNT ST
10th IN RAT HOLE (CIRCULATE) (CEMENTED BY SWD QNT.)
DID NOT PENETRATE STRUCTURE.

Remarks: _____

RECEIVED STATE CORPORATION COMMISSION

DEC 21 1982 12-21-82

CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 1-13-83
INV. NO. 2154-W

Signed Marion Schmidt (TECHNICIAN) DOIC