

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24292-00-00
Spot: S2N2SE Sec/Twnshp/Rge: 30-19S-23W
1585 feet from S Section Line, 1285 feet from E Section Line
Lease Name: KERR MR Well #: 1-30
County: NESS Total Vertical Depth: 4440 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 4436 WITH 200 SX CMT
SURF Size: 8.625 feet: 263 WITH 175 SX CMT

#144³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2005 9:10 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TUBING TO 1600', PUMP CEMENT TO SURFACE, PULL TUBING AND TOP OFF 5-1/2. CHECK 8-5/8" WITH 50 SX CMT. PRESSURE TO 500# AND SHUT IN.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2005 10:50 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

RUN TUBING TO 1600'. PUMPED 135 SX CMT & CIRCULATED CMT TO SURFACE.
PULLED TUBING & TOPPED OFF WITH 11 SX CMT. TIED ONTO BACKSIDE &
PUMPED 10 SX CMT. PRESSURED TO 500#.

Perfs:


Top	Bot	Thru	Comments
4395	4405		
4352	4358		

RECEIVED
APR 06 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Steve Durrant
(TECHNICIAN)

INVOICED
DATE 4-6-05
INV. NO. 2005061376