

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20633-00-01
Spot: SWNW Sec/Twnshp/Rge: 8-34S-34W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CLARK Well #: 8-2
County: SEWARD Total Vertical Depth: 6600 feet

Operator License No.: 31914
Op Name: CONTINENTAL RESOURCES, INC.
Address: PO BOX 1032
ENID, OK 73702

CIBP Size: feet: 6230 WITH 2 SX CMT
PKR Size: feet: 6259
PROD Size: 4.5 feet: 6600 WITH 300 SX CMT
SURF Size: 8.625 feet: 1680 WITH 900 SX CMT

#214⁵⁰

Well Type: EOR UIC Docket No: E27030.1 Date/Time to Plug: 03/31/2005 8:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 6230' & 1 SX CMT. PLUG AT 1710' WITH 50 SX CMT. PLUG AT 700' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 03/31/2005 4:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: JIM HOLLAND

Actual Plugging Report:

9/94: CASING LEAKS @ 3320-3351' WERE SQUEEZED & ANGUARDED. 1ST PLUG SET CIBP @ 6230' WITH 2 SX CMT. PACKER LEFT IN HOLE AT 6259'. 2ND PLUG PULL OUT OF HOLE TO 1710'. CIRCULATE HOLE WITH MUD. PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 700' LOAD HOLE & PUMP 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 4TH PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 6351 | 6358 | | |

RECEIVED
APR 06 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2020' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 4-6-05
VV. NO. 2005061374

[Signature]