

4-060722

8-9

API Number: 15-065-22,760 -00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C SW /4 SEC. 36, 06 S, 22 W
1320 feet from S section line
3960 feet from E section line

Operator license# 4629

Lease: Thurlow Well # 1-36

Operator: Brito Oil Co. & Vess Oil Co.

County: Graham 121.88

Address: 120 S. Market
Suite #300
Wichita, Kansas 67208

Well total depth 3750 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: L.D. Drilling, Inc. License# 6039

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 2:30 P.M. Day: 9 Month: August Year: 1995

Plugging proposal received from: Greg Davidson

Company: L.D. Drilling, Inc. Phone: 316-793-3051

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1995

CONSERVATION DIVISION
WICHITA, KANSAS

8-30-95

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 2:30 P.M., Day: 9, Month: August, Year: 1995

Actual plugging report:

- 1st. Plug at 1950' with 25 sxs. - Anhydrite 1930' - 1960'.
- 2nd. Plug at 1180' with 100 sxs. - Dakota 876' - 1176'.
- 3rd. Plug at 310' with 40 sxs. - Surface pipe to 257'.
- 4th. Plug at 40' with 10 sxs.
- Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO X
Plugged through TUBING, CASING. Elevation: 2276 GL

INVOICED

I did [] / did not [X] observe the plugging.

[Signature]
AK (agent)
Form CP-2/3

DATE 8-31-95
INV. NO. 43382