

15-065-21512-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_

SW, Sec. 31, T 6 S, R 22 <sup>(W)</sup>E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420

Lease Name LACERTE Well # 1-31

Operator: K.R.M. PETROLEUM CORP.  
Name &  
Address 1900 GRANT ST.  
SUITE 300  
DENVER CO. 80203

County GRAHAM

Well Total Depth 4050 feet 131.63

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 550

Address CHASE KANSAS

Company to plug at: Hour: AM Day: 5 Month: 5 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO DON COOL

(company name) KELSO CASING PULLING (phone) \_\_\_\_\_

were: BOTTOM PLUG - 5SX. COM. CEM. SAND ABOVE PERFORATIONS

5 SX. ON TOP - SHOOT AND PULL PIPE - RECOVERED 2426'  
OF 5 1/2" CASING - THERE WERE 4 SHOTS 3075-2879-2627-2426'

COM. CEM & SAND

Signed Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 PM Day: 5 Month: 5 Year: 19 83

ACTUAL PLUGGING REPORT BOTTOM PLUG AS ABOVE

TOP PLUG - SQUEEZED DOWN 8 5/8 WITH 2 SX. HULLS  
28 SX. GEL-100SX CEM. 12 SX. GEL-8 5/8 PLUG - 70 SX. CEM.

CEM > 50/50 POZ 6% GEL 3% CC

Remarks: MAX. 400 PSI SHUT IN 150 PSI

ELEV. 2367

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

Signed Carl Goodrow  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

DATE 5-19-83

MAY 16 1983

INV. NO. 4358-W

CONSERVATION DIVISION  
Wichita, Kansas