

To: **6 031217**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-6

API NUMBER 15-065-22445-00-00
50' N of _____
NW SW SW _____, SEC. 36, T 6 S, R 22 W/E
1040 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration Inc.
Name & Address 125 N. Market #1000
Wichita, Ks. 67202

Lease Name Thurlow Estate Well # 1
County Graham 124.80
Well Total Depth 3 840 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 6 Month: Jan Year: 19 89

Plugging proposal received from Mark
(company name) Kelso (phone) _____

were: 8 5/8" set at 254' w/165 sks. 4 1/2" set at 3830' w/125 sks. PBDT 3810'
Perf 3685' - 3678'. Order sand and common cement. Pull pipe. Order 200 sks 65/35 Poz 10%
gel 2% Dixel 500# Hulls. Allied Cement Co. Keller Water Trucks. Run wireline to anyh.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15AM Day: 6 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3625' w/4 sks common cement on sand w/
bailer. One shot recovered 3000' of 4 1/2" casing. Hole open to anyh. Squeezed 8 5/8" of 200 sks
cement blend w/500# Hulls mixed into max psi 600#. Close in psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
1-27-89
JAN 27 1989

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

I (did not observe) observe this plugging.

INVOICED
DATE 2-02-89
INV. NO. 2383X
Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow