

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22858-00-00  
Spot: N2N2SW Sec/Twnshp/Rge: 34-6S-22W  
2290 feet from S Section Line, 3930 feet from E Section Line  
Lease/Unit Name: WORCESTER Well Number: 1  
County: GRAHAM Total Vertical Depth: 3775 feet

Operator License No.: 32781  
Op Name: ROBERTS RESOURCES, INC.  
Address: 520 S. HOLLAND - SUITE 207  
WICHITA, KS 67209

Conductor Pipe: Size feet: \$122.69  
Surface Casing: Size 8.625 feet: 267  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 11/11/2001 12:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 11/11/2002 1:00 PM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1975' w/25 sxs. Anhydrite 1949' - 1981'.  
2nd. Plug at 1200' w/100 sxs. Dakota 901' - 1201'.  
3rd. Plug at 325' w/40 sxs. Surface pipe to 267'.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

NOV 18 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature]

(TECHNICIAN)

INVOICED

DATE 11-19-02

INV. NO. 2003060830

Form CP-2/3

NOV 14 2002