

031472

12-9

275
P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,609 -00-00

SW NW SESEC. 34, T 6 S, R 22 W/Ex

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030

Lease Name Worchester Well # 1

Operator: Ainsworth Operating Co.
Name & Address Box 1269
Colorado Springs, Co. 80901

County Graham 124.96

Well Total Depth 3845 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 9 Month: Dec. Year: 19 90

Plugging proposal received from Harold Maley

(company name) Abercrombie (phone)

were: 8 5/8 set at 264 w/190 sks cwc. Circ hole w/no less than 36 vis.

Mud w/no loss or gain offfluid. Keep hole full and balance plugs w/mud.

Order 190 sks 60/40 poz 6% gel 3% cc. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 1:00 PM Day: 9 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drilling pipe w/25 sks at 1950

100 sks at 1150 w/hulls

40 sks at 315

10 sks at 40 w.p.

Circ 15 sks in rathole.

Stamp: CONSERVATION DIVISION
Wichita, Kansas
1-4-91

Remarks: Elev. 2282 GL Anhy 1934 - 65

(If additional description is necessary, use BACK of this form.)

INVOICED

(if xxx did not) observe this plugging.

DATE JAN 22 1991

INV. NO. 30543

J.S.

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow