

To: 6 031230
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-21,916-0060

SW SE SW, SEC. 30, T. 6 S, R. 22 W
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Operator: Davis Petroleum Inc.
Name & Address: R. R. 1 Box 183 B
Great Bend, Ks. 67530

Lease Name Fountain Well # 1-30
County Graham 130.33
Well Total Depth 4010 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number _____

Address Box 768 Great Bend, Ks. 67530

Company to plug at: Hour: PM Day: 21 Month: Mar Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) _____

were: 8 5/8" set at 250' w/200 sks cwc. 5 1/2" set at 3985' w/150 sks. Perf 3578' - 84'.

Order sand and common cement. Pull pipe. Order 225 sks ATL 65/35 Poz 10% Gel 2% Dical 500# Hulls. Allied Cement Co. Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 PM Day: 21 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3530' w/5 sks common cement on sand w/bailer.

4 shots recovered 818' of 5 1/2" casing from 1849'; 1300'; 1109' and 818'. Squeezed 8 5/8" w/225 sks cement blend w/500# Hulls mixed into max psi 900#. Cement 300#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1989
3-29-89

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOLVED
did not observe this plugging.

DATE 4-19-89
WV. NO. 24328

gfs

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow