

4-090526

12-6

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,752-00-00

NE NE NE /4 SEC. 27, 06 S, 22 W
4950 feet from S section line
330 feet from E section line

Operator license# 4767

Lease FTB Homestead Trust well # 1

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67202

Well total depth 3780 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 219 feet

122,85

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Duke Drilling License# -

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 5 Month: December Year: 94

Plugging proposal received from: Jerry Heiderscheit

Company: Duke Drilling Phone: -

Were: Order 185 sxs. 60/40 posmix - 6% gel - 1 sx. celloflake.
Spot all plugs through drill pipe with heavy mud between all
plugs.

Plugging Proposal Received by: Ed Schumacher
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:45A.M., Day: 6, Month: December, Year: 94

Actual plugging report:

- 1st. plug at 1980' w/20 sxs.
- 2nd. plug at 1205' w/100 sxs.
- 3rd. plug at 270' w/40 sxs.
- 4th. plug at 40' w/10 sxs.
- 15 sxs. in rathole.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 19 1994

Arbuckle - No.

CONSERVATION DIVISION
WICHITA, KS

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES 1976 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2303 GL

12-19-94

I did did not X observe the plugging.

Ed Schumacher

(agent)

Form CP-2/3

INVOICED

DATE

1-5-95

INV. NO.

41972