

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22798-00-00
Spot: SENWSW Sec/Twnshp/Rge: 26-6S-22W
1680 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: MCCAULEY Well Number: 1
County: GRAHAM Total Vertical Depth: 3890 feet

Operator License No.: 4767

Conductor Pipe: Size feet:

Op Name: RITCHIE EXPLORATION, INC.

Surface Casing: Size 8.625 feet: 226

Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Production: Size feet:

Liner: Size feet:

126.43

Well Type: DH

UIC Docket No:

Date/Time to Plug: 12/17/2000 11:00 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: BILL

Company: MURFIN DRILLING CO., INC.

Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/17/2000 3:00 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2025' w/25 sxs. Anhydrite 1984' - 2015'.
2nd. Plug at 1225' w/100 sxs. Dakota 910' - 1210'.
3rd. Plug at 280' w/40 sxs. Surface Pipe 226'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed _____

RECEIVED
(TECHNICIAN)
KANSAS CORPORATION COMMISSION

INVOICED

DATE 12/27/00

WV. NO. 2001061201

DEC 27 2000

Form CP-2/3

DEC 22 2000

CONSERVATION DIVISION
WICHITA, KS