

6-22-88

To: 6 070692  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,465-00-00  
NE NE NW, SEC. 26, T 6 S, R 22 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

4950 feet from S section line

2970 feet from E section line

Lease Name Keiswetter Well # 26-B #1

Operator: Ritchie Exploration Inc.

County Graham 127.99

Name & Address 125 N. Market #1000

Well Total Depth 3938 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Jeff Christian

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A  X

Other well as hereinafter indicated Tag #604

Plugging Contractor Murfin Drilling Company License Number 6033

Address Wichita, Ks. 67101

Company to plug at: Hour: 5:15 PM Day: 22 Month: June Year: 19 88

Plugging proposal received from Lloyd Dellelette

(company name) Murfin Drilling Co. (phone) \_\_\_\_\_

were: 8 5/8" - 253' S.P. cwc w/175 sks 60/40 Poz 2% Gel 3% Ca Cl. By Allied.

Elevation 2373', Anhy 2031', Arbuckle 3900'. No circulation problems. Mud condition 43 viscosity - 9.6 weight - water 10. Proposal 225 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk F.C. and 8 5/8" plug. Spot with drill stem, circulate, heavy mud between all plugs; 25 sks at 3870' 25 sks 2050', 100 sks at 1270'; 50 sks at 300', 10 sks at 40' - 15 sks in rat hole (circulate)

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None  X

Operations Completed: Hour: 5:15PM Day: 22 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 3% Ca Cl. 1 sk F.C. and 8 5/8" plug. Spotted with drill stem with heavy mud between all plugs.

1st plug 25 sks at 3870'. 2nd plug 25 sks at 2050'.

3rd plug 100 sks w/1 F.C. at 1270' 4th plug 50 sks at 300'.

5th plug Hulls, plug at 40' w/10 sks cement 15 sks in rat hole (circulate)

Remarks: Cemented by Allied Cement

(If additional description is necessary, use BACK of this form.)

(If you did not observe this plugging.)

DATE 7-8-88

Signed Marion J. Schmidt  
Marion J. Schmidt (TECHNICIAN)

INV. NO. 21240  
6-22