

6 040307

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,126 *0000*
SW NW NW, SEC. 26, T. 6 S, R. 22 W/EX
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562
Operator: Liberty Operations & Completions
Name & Address: 308 West Mill
Plainville, Ks. 67663

Lease Name Keiswetter Well # 1
County Graham 130.23
Well Total Depth 4007 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 261 w/170

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilling License Number 5665
Address Plainville, Ks.

Company to plug at: Hour: 12:00 PM Day: 6 Month: 1 Year: 19 85

Plugging proposal received from John Walker

(company name) Pioneer Drilling (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 2 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by *Dennis L. Hamel*
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 12:00 PM Day: 6 Month: 1 Year: 19 85

ACTUAL PLUGGING REPORT

- 1st plug @ 2025 w/40 sks
- 2nd plug @ 1200 w/100 sks w/2 sks hulls
- 3rd plug @ 275 w/40 sks
- 4th plug @ 40 w/10 sks Solid bridge
- 10 sks in Rat Hole

1-17-85
RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1985

Remarks: _____ CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I (did / did not) observe this plugging.

DATE 1-28-85

INV. NO. 6656

Signed *Dennis L. Hamel*
(TECHNICIAN)

23
Jan 16 - 85
mjs