

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22452-00-01
Spot: S2SESE Sec/Twnshp/Rge: 13-6S-23W
510 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: F&M BANK Well Number: 1
County: GRAHAM Total Vertical Depth: 3820 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet: 124.15
Surface Casing: Size 8.625 feet: 260 w/185 sxs cmt
Production: Size 4.5 feet: 3805 w/160 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/13/2002 1:00 PM
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 420 cu.ft. cement slurry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/13/2002 2:15 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 260' w/185 sxs cwc.
4 1/2" set at 3805' w/160 sxs.
Prod. Perfs 3586' - 3589'; 3602' - 3605'.
Top stage cement information N/A.
Filled hole with 420 cu.ft. cement slurry.
Plug complete.

RECEIVED
FEB 22 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

FEB 22 2002

INVOICED
DATE Feb 28-02
INV. NO. 2002061425

Form CP-2/3

STATE: KANSAS COUNTY: GRAHAM REISSUE OWWO 13-6S-23W
FIELD: MOUNT VERNON NORTH S2 SE SE
OPER: RITCHIE EXPL 510 FSL 660 FEL SEC
WELL: 1 F&M BANK WELL CLASS: WSD ELEV: 2363 KB
API: 15-065-22452-0001 STATUS: OIL-WO 2358 GR
SPUD: 11/28/90 COMP: 11/30/90
DTD: 3820 LTD: FTD: ARBUCKLE PBTD:

LOC: 10 1/2 MI N HILL CITY, KS

IP: COMP 11/30/90, IPP 4 BO, 90 BWPD **PROD ZONE**- TORONTO 3586-3589
LANSING-KC 3602-3605 COMMINGLED FIRST REPORT & COMPLETION (TORONTO
DISCOVERY - SHALLOWER POOL)

TBG: 2 3/8 @ 3756;

OWWO: OWWO: OLD INFO: FORMERLY RITCHIE EXPL 1 F&M BANK. SPUD 7/20/88. 8 5/8 @
260 W/185 SX, 4 1/2 @ 3805 W/160 SX. LOG TOPS: TORONTO 3586, LANSING 3602,
BSE KANSAS CITY 3796. OTD 3820. COMP 10/27/88. IPP 15 BO, 130 BWPD. PROD
ZONE: LANSING 3602-3605.

PERFS: PERF (TORONTO) 3586-3589 W/3 PF, ACID W/500 GALS, 15% NE,
PRODUCING INTERVAL: PERF (TORONTO) 3586-3589, PERF (LANSING-KANSAS CITY)
3602-3605,

OPER ADD: 125 N MARKET STE 1000, WICHITA, KS, 67202 PHONE (316) 267-4375;

CONTR: NOT RPTD

REISSUE TO ADD NEWLY RELEASED CONFIDENTIAL DATA REPLACEMENT FOR CARFD
ISSUED 4/9/91

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 04/03/92 CARD #00055-KS