

10-1-87

6 030960

API NUMBER 15- 15-065-22,399 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW NW, SEC. 12, T 6 S, R 23 W Ex

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3153

Lease Name Nighswonger Well # 12-1

Operator: Cardwell and Parker
Name & Address: Box 1721
Plano, Texas 75074

County Graham 128.38

Well Total Depth 3950 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 332 w/190 sk

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling Company License Number 5107

Address Wichita, Kansas

Company to plug at: Hour: _____ PM Day: 1 Month: October Year: 19 87

Plugging proposal received from Dick Davis

(company name) H-30 (phone) _____

were: Order 190 sks 60/40 Pozmix 6% Gel 3% Cal Cl 1 sk Hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss. Allied Cement Company.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:15 PM Day: 1 Month: October Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 2025' w/25 sks

2nd plug at 1150' w/100 sks and 1 sk Hulls

3rd plug at 380' w/40 sks

4th plug at 40' w/10 sks; wiper plug.

15 sks in rat hole Elev. 2347' Anhy 2002' - 2032'

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1987
10-23-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Contractor did not observe this plugging.

DATE 10-26-87
INV. NO. 18651

Signed *Carl Goodrow*
(TECHNICIAN)
Carl Goodrow