

7-15-89  
API NUMBER 15- 15-065-22,523 -00-00

6 100393

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW SE, SEC. 1, T. 6 S, R. 23 W/E

2310 feet from S section line

2310 feet from E section line

Lease Name Donald Smith Well # 1

County Graham 123.01

Well Total Depth 3785 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration Inc.

Name & Address 125 North Market

Sutie 1000

Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address Wichita, Ks. 67202

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Co (phone)

were: Spot plugs through drill pipe w/heavy mud between all plugs.

1st plug at 2000' w/25 sks Rathole 15 sks

2nd plug at 1195' w/100 sks Mousehole 10 sks

3rd plug at 310' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

Plugging Proposal Received by David K. Wann (TECHNICIAN) X

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:00AM Day: 15 Month: July Year: 19 89

ACTUAL PLUGGING REPORT Order 200 sks 60/40 poz w/6% gel and 2 sks cello

flake/flowcel. Hole reported plugged as above.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 15 1989

10-20-89

Elevation 2344' GL, Anhydrite depth: 1986' - 2012'.

Remarks: Did not penetrate Arbuckle, Cemented by Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify that I have observed this plugging.

DATE 10-25-89

INV. NO. 26239

7-15 NOV 06 1989

Signed David K. Wann (TECHNICIAN)