

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065 - 22,015-00-00
C NW SE Sec. 3 , T 6 S, R 23 W/4
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Kemper Well # D-1

Operator: F&M Oil Company
Name & 422 Union Center
Address Wichita, Ks. 67202

County Graham

Well Total Depth 4015 feet 130.49

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Union Drlg. Company License Number 5103 Rig Tag 4

Address Same as above

Company to plug at: Hour: 4 am Day: 28 Month: July Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Lyle Cofon

(company name) Union Drlg. Company (phone) _____

were: Order 210 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation.

Signed _____
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 2:15 AM Day: 28th Month: July Year: 19 84

ACTUAL PLUGGING REPORT _____

1st plug @ 3990 w/25 sks

2nd plug @ 2040 w/25 sks

3rd plug @ 1280 w/100 sks 1 sk flo-cel

4th plug @ 450 w/40 sks

5th plug @ 40 w/8 5/8" plug 1/2 sk hulls and 10 sks cement

10 sks in Rat Hole

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
AUG 06 1984
8-6-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed Gilbert P. Leiker
(TECHNICIAN)

INVOICED

DATE 8-13-84

INV. NO. 2973

8-3-84