

3-29 150 P

6 062119

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,560-00-00P
SE, SEC. 2, T 6 S, R 23 W/E
2310 feet from S section line
350 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration Inc.
Name & Address 125 N. Market Suite 1000
Wichita, Ks. 67202

Lease Name Schuck 2D Well # 1
County Graham 71.18
Well Total Depth 2190 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 249' w/160 sk

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated Anh Dropped 50'

Plugging Contractor Murfin Drilling Co. License Number _____
Address Wichita, Ks.

Company to plug at: Hour: 7:30AM Day: 29 Month: Mar Year: 19 90

Plugging proposal received from Lloyd Dellet
(company name) Murfin Drilling Co. (phone) 316-267-4375

were: Order 200 sks 60/40 poz 6% gel 3\$\$\$ cal cl 1 sl f.c. and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis mud between all plugs with good
circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00PM Day: 29 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT
1st plug at 2050' w/25 sks.
2nd plug at 1200' w/100 sks 1 sk f.c.
3rd plug at 300' w/40 sks
4th plug at 40' w/10 sks
15 sks in rthaole 10 sks in mousehole

Remarks: Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-6-90
WV. NO. 32809
3-29

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck