

4 060133

11-12

API NUMBER 15-065-22,605-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SW, SEC. 1, T 6 S, R 23 W/R

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name John Kemper Well # 4

Operator: Ritchie Exploration Inc.
Name & Address 125 N. Market, Suite 1000
Wichita, KS 67202

County Graham 123.17

Well Total Depth 3790 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 1:45PM Day: 12 Month: November Year: 19 90

Plugging proposal received from Lloyd Delett

(company name) Murfin Drilling Co. (phone) _____

were: Order 200 sxs. 60/40 pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXX

Operations Completed: Hour: 1:45PM Day: 12 Month: November Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2075' with 25 sxs. Anhydrite 2052-2082'

2nd plug at 1200' with 100 sxs. Dakota 895-1195'

3rd plug at 310' with 40 sxs. Surface pipe to 260'

4th plug at 40' with 10 sxs.

rathole with 15 sxs. mousehole with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

NOV 21 1990
11-21-90

Remarks: Allied Cementing
(if additional description is necessary, use BACK of THIS FORM.)
1 (XXXX did not) observe this plugging.

INVOICED

DATE NOV 27 1990

WV. NO. 30043

Signed Herb Deines
(TECHNICIAN)

Herb Deines