

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20380-00-00
Spot: SENW Sec/Twnshp/Rge: 27-21S-7W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: WILSON Well #: 1
County: RICE Total Vertical Depth: 3430 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3416 75 SX CMT
SURF Size: 8.625 feet: 173 160 SX CMT

#11148

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2005 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE FUNK Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Sand off perforations to 3340' and put 5 sacks of cement on top. Cut off casing. Pull to 1025' and pump 35 sacks of cement. Pull to 575' and pump 35 sacks of cement. Pull casing to 250' and circulate cement to surface.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 03/14/2005 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded off perforations to 3340' and put 5 sacks of cement on top. Cut off casing at 1530'. Pulled to 1025' and pumped 35 sacks of cement. Pulled to 575' and pumped 35 sacks of cement. Pulled casing to 250' and circulated cement to surface.

Copeland Cement #24932

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3417	3430		
3393	3399		

RECEIVED
KCC DISTRICT #2
MAR 31 2005
WICHITA, KS

RECEIVED
APR 11 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 4-12-05
2005061395